




LEGEND:

- "B.L." INDICATES BUILDING LINE
- "H.C.M.R." INDICATES HARRIS COUNTY MAP RECORDS
- "H.C.C.F." INDICATES HARRIS COUNTY CLERKS OFFICE
- "H.C.D.R." INDICATES HARRIS COUNTY DEED RECORDS
- "R.O.W." INDICATES RIGHT-OF-WAY
- "(VOL./PG.)" INDICATES RECORDED VOLUME/PAGE
- "o" INDICATES IRON ROD SET
- "•" INDICATES IRON ROD FOUND
- "ESMT." INDICATES EASEMENT
- "H" INDICATES EXISTING FIRE HYDRANT

PLAT NOTES:

- LOTS 1-16, BLOCK 1 ARE RESTRICTED TO SINGLE FAMILY RESIDENTIAL USE.
- SINGLE FAMILY RESIDENTIAL SHALL MEAN THE USE OF A LOT WITH ONE BUILDING DESIGNED FOR AND CONTAINING NOT MORE THAN TWO SEPARATE UNITS WITH FACILITIES FOR LIVING, SLEEPING, COOKING, AND EATING THEREIN. A LOT UPON WHICH IS LOCATED A FREE-STANDING BUILDING CONTAINING ONE DWELLING UNIT AND A DETACHED SECONDARY DWELLING UNIT OF NOT MORE THAN 900 SQUARE FEET ALSO SHALL BE CONSIDERED SINGLE FAMILY RESIDENTIAL. A BUILDING THAT CONTAINS ONE DWELLING UNIT ON ONE LOT THAT IS CONNECTED BY A PARTY WALL TO ANOTHER BUILDING CONTAINING ONE DWELLING UNIT ON AN ADJACENT LOT SHALL BE SINGLE FAMILY RESIDENTIAL.
- EACH LOT SHALL PROVIDE A MINIMUM OF TWO OFF-STREET PARKING SPACES PER DWELLING UNIT ON EACH LOT. IN THOSE INSTANCES WHERE A SECONDARY UNIT IS PROVIDED ONLY ONE ADDITIONAL SPACE SHALL BE PROVIDED.
- UNLESS OTHERWISE INDICATED, THE BUILDING LINES, WHETHER ONE OR MORE, SHOWN ON THIS SUBDIVISION PLAT ARE ESTABLISHED TO EVIDENCE COMPLIANCE WITH THE APPLICABLE PROVISIONS OF CHAPTER 42, CODE OF ORDINANCES, CITY OF HOUSTON, TEXAS, IN EFFECT AT THE TIME THIS PLAT WAS APPROVED, WHICH MAY BE AMENDED FROM TIME TO TIME.
- THIS SUBDIVISION CONTAINS ONE OR MORE PERMANENT ACCESS EASEMENT THAT HAVE NOT BEEN DEDICATED TO OR ACCEPTED BY THE CITY OF HOUSTON OR ANY OTHER LOCAL GOVERNMENT AGENCY AS PUBLIC RIGHTS-OF-WAY. THE CITY OF HOUSTON HAS NO OBLIGATION, NOR DOES ANY OTHER LOCAL GOVERNMENT AGENCY HAVE ANY OBLIGATION, TO MAINTAIN OR IMPROVE ANY SHARED DRIVEWAYS WITHIN THE SUBDIVISION, WHICH OBLIGATION SHALL BE THE SOLE RESPONSIBILITY OF THE OWNERS OF PROPERTY IN THIS SUBDIVISION.
- AT LEAST 150 SQUARE FEET OF PERMEABLE AREA IS REQUIRED PER LOT, 2,400 S.F. OF PERMEABLE AREA SHALL BE PROVIDED WITHIN THE BOUNDARY OF THIS SUBDIVISION, REFERENCE 42-1 PERMEABLE AREA DEFINITION.
- THE NUMBER OF SINGLE FAMILY RESIDENTIAL DWELLING UNITS THAT CAN BE CONSTRUCTED SHALL NOT EXCEED AN EQUIVALENT DENSITY OF 27 UNITS TO THE GROSS ACRE OF ALL LAND WITHIN THE BOUNDARIES OF THIS SUBDIVISION PLAT.
- ALL LOTS SHALL HAVE ADEQUATE WASTEWATER COLLECTION SERVICE.
- THE COORDINATES SHOWN HEREON ARE TEXAS SOUTH CENTRAL ZONE NO. 4204 STATE PLANE GRID COORDINATES (NAD83) AND MAY BE BROUGHT TO SURFACE BY APPLYING THE FOLLOWING COMBINED SCALE 0.999880.
- THE RESIDENTIAL LOTS LOCATED IN THIS SUBDIVISION ARE NOT ELIGIBLE FOR SOLID WASTE COLLECTION SERVICES BY THE CITY AT THE TIME OF THE FILING OF THE PLAT. NOTWITHSTANDING THE FOREGOING, THE CITY RESERVES THE RIGHT TO AMEND THE LEVEL OF SOLID WASTE COLLECTION SERVICES IT PROVIDES.
- N/A
- NO BUILDING PERMIT OR OTHER PERMIT, EXCEPT PERMITS FOR CONSTRUCTION OF PUBLIC IMPROVEMENTS, WILL BE ISSUED BY THE CITY OF HOUSTON, TEXAS, FOR CONSTRUCTION WITHIN THE SUBDIVISION UNTIL SUCH TIME AS THE FUNDS REQUIRED UNDER PROVISIONS OF SECTION 42-253 OF THE CODE OF ORDINANCES OF THE CITY OF HOUSTON, TEXAS, HAS BEEN SUBMITTED AND ACCEPTED BY THE CITY.
- THIS PERCENTAGE IS (100%) SHALL BE APPLIED TO THE THEN-CURRENT FEE IN LIEU OF DEDICATION.
- THE THEN-CURRENT FEE IN LIEU OF DEDICATION SHALL BE APPLIED TO THIS NUMBER (26 UNITS) OF DWELLING UNITS.
- NO LAND IS BEING ESTABLISHED AS PRIVATE PARK OR DEDICATED TO THE PUBLIC FOR PARK PURPOSES.
- THIS PROPERTY IS LOCATED IN PARK SECTOR NUMBER 1.
- ABSENT WRITTEN AUTHORIZATION BY THE AFFECTED UTILITIES, ALL UTILITY AND AERIAL EASEMENTS MUST BE KEPT UNOBSTRUCTED FROM ANY NON-UTILITY IMPROVEMENTS OR OBSTRUCTIONS BY THE PROPERTY OWNER. ANY UNAUTHORIZED IMPROVEMENTS OR OBSTRUCTIONS MAY BE REMOVED BY ANY PUBLIC UTILITY AT THE PROPERTY OWNER'S EXPENSE. WHILE WOODEN POSTS AND PANELED WOODEN FENCES ALONG THE PERIMETER AND BACK TO BACK EASEMENTS AND ALONGSIDE REAR LOTS LINES ARE PERMITTED, THEY TOO MAY BE REMOVED BY PUBLIC UTILITIES AT THE PROPERTY OWNER'S EXPENSE SHOULD THEY BE AN OBSTRUCTION. PUBLIC UTILITIES MAY PUT SAID WOODEN POSTS AND PANELED WOODEN FENCES BACK UP, BUT GENERALLY WILL NOT REPLACE WITH NEW FENCING.
- ALL PRIVATE STREETS SHOWN HEREIN ARE ALSO PERMANENT ACCESS EASEMENT.
- THIS SUBDIVISION HAS A PRIVATE WATER SYSTEM. IT IS NOT A PUBLIC WATER SYSTEM, NOR WILL IT BE CONSTRUCTED WITH ANY PUBLIC FUNDS. THE WATER LINE AND FIRE HYDRANTS THAT WILL SERVE THIS SUBDIVISION ARE PRIVATE AND WILL BE MAINTAINED BY THE OWNER AND/ OR OWNER'S MANAGEMENT ASSOCIATION.

STATE OF TEXAS
COUNTY OF HARRIS

WE, 604 MARTIN, LLC, ACTING BY AND THROUGH MIKE HO, ITS MANAGING MEMBER, OWNERS HEREAFTER REFERRED TO AS OWNERS OF THE 0.999 ACRE TRACT DESCRIBED IN THE ABOVE AND FOREGOING MAP OF MARTIN COURT, DO HEREBY MAKE AND ESTABLISH SAID SUBDIVISION AND DEVELOPMENT PLAN OF SAID PROPERTY ACCORDING TO ALL LINES, DEDICATIONS, RESTRICTIONS, AND NOTATIONS ON SAID MAPS OR PLAT AND HEREBY DEDICATE TO THE USE OF THE PUBLIC FOREVER, ALL STREETS (EXCEPT THOSE STREETS DESIGNATED AS PRIVATE STREETS, OR PERMANENT ACCESS EASEMENTS), ALLEYS, PARKS, WATER COURSES, DRAINS, EASEMENTS AND PUBLIC PLACES SHOWN THEREON FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED; AND DO HEREBY BIND OURSELVES, OUR HEIRS, SUCCESSORS AND ASSIGNS TO WARRANT AND FOREVER DEFEND THE TITLE ON THE LAND SO DEDICATED.

FURTHER, OWNERS HAVE DEDICATED AND BY THESE PRESENTS DO DEDICATE TO THE USE OF THE PUBLIC FOR PUBLIC UTILITY PURPOSE FOREVER UNOBSTRUCTED AERIAL EASEMENTS. THE AERIAL EASEMENTS SHALL EXTEND HORIZONTALLY AN ADDITIONAL ELEVEN FEET, SIX INCHES (11' 6") FOR TEN FEET (10' 0") PERIMETER GROUND EASEMENTS OR SEVEN FEET, SIX INCHES (7' 6") FOR FOURTEEN FEET (14' 0") PERIMETER GROUND EASEMENTS OR FIVE FEET, SIX INCHES (5' 6") FOR SIXTEEN FEET (16' 0") PERIMETER GROUND EASEMENTS, FROM A PLANE SIXTEEN FEET (16' 0") ABOVE THE GROUND LEVEL UPWARD, LOCATED ADJACENT TO AND ADJOINING SAID PUBLIC UTILITY EASEMENTS THAT ARE DESIGNATED WITH AERIAL EASEMENTS (U.E. AND A.E.) AS INDICATED AND DEPICTED HEREON, WHEREBY THE AERIAL EASEMENT TOTALS TWENTY ONE FEET, SIX INCHES (21' 6") IN WIDTH.

FURTHER, OWNERS DO HEREBY DECLARE THAT ALL PARCELS OF LAND DESIGNATED AS LOTS ON THIS PLAT ARE ORIGINALLY INTENDED FOR THE CONSTRUCTION OF SINGLE FAMILY RESIDENTIAL DWELLING UNITS THEREON (OR THE PLACEMENT OF MOBILE HOME SUBDIVISION) AND SHALL BE RESTRICTED FOR SAME UNDER THE TERMS AND CONDITIONS OF SUCH RESTRICTIONS FILED SEPARATELY.

FURTHER, OWNERS DO HEREBY COVENANT AND AGREE THAT ALL OF THE PROPERTY WITHIN THE BOUNDARIES OF THIS PLAT IS HEREBY RESTRICTED TO PREVENT THE DRAINAGE OF ANY SEPTIC TANKS INTO ANY PUBLIC OR PRIVATE STREET, PERMANENT ACCESS EASEMENT, ROAD OR ALLEY, OR ANY DRAINAGE DITCH EITHER DIRECTLY OR INDIRECTLY.

FURTHER, OWNERS DO HEREBY DEDICATE TO THE PUBLIC A STRIP OF LAND FIFTEEN FEET (15' 0") WIDE ON EACH SIDE OF THE CENTER LINE OF ANY AND ALL BAYOUS, CREEKS, GULLIES, RAVINES, DRAWS, SLOUGHS, OR OTHER NATURAL DRAINAGE COURSES LOCATED IN SAID PLAT, AS EASEMENTS FOR DRAINAGE PURPOSES, GIVING THE CITY OF HOUSTON, HARRIS COUNTY, OR ANY OTHER GOVERNMENTAL AGENCY, THE RIGHT TO ENTER UPON SAID EASEMENT AT ANY AND ALL TIMES FOR THE PURPOSE OF CONSTRUCTION AND MAINTENANCE OF DRAINAGE FACILITIES AND STRUCTURES.

FURTHER, OWNERS DO HEREBY COVENANT AND AGREE THAT ALL OF THE PROPERTY WITHIN THE BOUNDARIES OF THIS PLAT SPECIFICALLY NOTED AS PRIVATE STREETS OR PERMANENT ACCESS EASEMENTS SHALL BE HEREBY ESTABLISHED AND MAINTAINED AS PRIVATE STREETS OR PERMANENT ACCESS EASEMENTS BY THE OWNERS, HEIRS, SUCCESSORS, AND ASSIGNS TO PROPERTY LOCATED WITHIN THE BOUNDARIES OF THIS PLAT AND ALWAYS AVAILABLE FOR THE GENERAL USE OF SAID OWNERS AND TO THE PUBLIC FOR FIREFIGHTERS, FIRE FIGHTING EQUIPMENT, POLICE AND EMERGENCY VEHICLES OF WHATEVER NATURE AT ALL TIMES AND DO HEREBY BIND OURSELVES, OUR HEIRS, SUCCESSORS AND ASSIGNS TO WARRANT AND FOREVER DEFEND THE TITLE TO THE LAND SO DESIGNATED AND ESTABLISHED AS PRIVATE STREETS OR PERMANENT ACCESS EASEMENTS.

FURTHER, OWNERS HEREBY CERTIFY THAT THIS REPLAT DOES NOT ATTEMPT TO ALTER, AMEND, OR REMOVE ANY COVENANTS OR RESTRICTIONS; WE FURTHER CERTIFY THAT NO PORTION OF THE PRECEDING PLAT WAS LIMITED BY DEED RESTRICTION TO RESIDENTIAL USE FOR NOT MORE THAN TWO (2) RESIDENTIAL UNITS PER LOT.

IN TESTIMONY WHEREOF, 604 MARTIN, LLC HAS CAUSED THESE PRESENTS TO BE SIGNED BY MIKE HO, ITS MANAGING MEMBER, THEREUNTO AUTHORIZED, THIS 15 DAY OF December, 2020.

604 MARTIN, LLC
A TEXAS LIMITED LIABILITY COMPANY

BY: *Mike H*
MIKE HO, MANAGING MEMBER

STATE OF TEXAS
COUNTY OF HARRIS

BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED MIKE HO, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT THEY EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED.

GIVEN UNDER MY HAND AND SEAL OF OFFICE, THIS 15 DAY OF December, 2020.

Esperanza E. Vega
NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS

PRINT NAME: *Esperanza E. Vega*

MY COMMISSION EXPIRES: April 24, 2023

MARTIN COURT

SUBDIVISION OF A 0.999-ACRE TRACT OF LAND, BEING ALL OF LOT 64, YALE STREET ACRES, ACCORDING TO THE MAP OR PLAT THEREOF RECORDED IN VOLUME 572, PAGE 523 OF THE DEED RECORDS OF HARRIS COUNTY, TEXAS.

BLOCKS: 1 LOTS: 16 RESERVES: 4

REASON FOR REPLAT: TO CREATE SIXTEEN (16) LOTS AND FOUR (4) RESERVES

DECEMBER, 2020

OWNER:
604 MARTIN, LLC
A TEXAS LIMITED LIABILITY COMPANY
6101-B AIRLINE DRIVE
HOUSTON, TEXAS 77076

SURVEYOR:
GREENLEAF LAND SURVEYS, LLC
10900 NORTHWEST FWY, SUITE 129
HOUSTON, TEXAS 77092
TEXAS FIRM REGISTRATION NO. 10193977

RECORDER'S MEMORANDUM:
At the time of recording, this instrument was found to be inadequate for the best photographic reproduction because of illegibility, carbon or photo copy, discolored paper, etc. All blackouts, additions and changes were present at the time the instrument was filed and recorded.

The
INTERFIELD GROUP
engineering | architecture
*401 STUDEWOOD, SUITE 300 TEL: (713) 780-0909
HOUSTON, TEXAS 77007 TX REG. NO. F-5611
WWW.INTERFIELD.NET
(INTERFIELD PROJ. #: 19116.00)